Omschrijving: PBW-Slopen Doc Type: XP Procedure

Doc. No: XP-452-W-0-00013 Document Versie: 04

SAFETY REGULATION VV 13  Demolish	nyrstar Balen/Pelt
Date of last modification:	03/01/203
Nature of last modification: See blue text	

When carrying out demolition work, the work permit must be accompanied by this completed requirement for demolition work.

RISKS				
Instability of the remaining adjacent parts of the demolition object (risk due to vibrations, wind forces)				
The formation of noxious, nuisance or flammable vapours, gases and dust and exp	olosive mixt	ures with air		
Unsafe working conditions in adverse weather conditions				
Falling or flying objects				
Fire risk: indicate fire-hazardous work on the work permit				
CONDITIONS THAT MUST BE MET BEFORE THE WORK CAN TAKE PLACE:	ACTION BY	PARAPHRASE UITV.		
Carry out a thorough risk analysis. Check whether the object to be demolished falls under the legislation of TMB				
Research condition and construction demolition objects				
For work below ground level consult VV 11				
Control of substances containing asbestos. If present, consult VV 26.				
check the presence of dangerous objects, substances gases.				
Control presence of ionizing sources. ConsultVV12				
Controlling dust emissions during demolition works.				
If necessary: preliminary consultations with utilities and competent public authorities				
Draw up demolition follow-up plan with declaration of conformity (SOP) incl. waste disposal plan by following the traceability procedure (working method, means, safety measures, escape routes, selective collection and disposal of demolition material, disposal tests). If demolition volume > 1000 m³, a demolition expert must be appointed.				
Disconnection/shielding and marking of process and utility lines to be left intact (process/gas/electricity/water/telephone/sewer systems)				
Removal of flammable liquids and gases.				
Cleaning of closed vessels and/ortanks. (certificate?)				
Struts, struts or spouts of adjacent parts				
Additional shielding:				
☐ Dropping off danger zones/applying warning signs				
Verification of inspection certificates for demolition material				

Proces: VEILIGHEID EN GEZONDHEID Blz. 1 of 2

Subproces: PBW V-VOORSCHRIFTEN BIJ WERKEN

Omschrijving: PBW-SlopenDoc. No: XP-452-W-0-00013Doc Type: XP ProcedureDocument Versie: 04

AFETY REQUIREMENT VV13  Demolish			r	nyrstar Balen/Pelt	
Performing measure	ements				
MEASUREMENT	METHOD	FREQUENCY	MEASURED VALUE		
DECLUBED DECTECTIVE	FOLUDMENT: Fill in part 1D o	on the work normit			

Proces: VEILIGHEID EN GEZONDHEID BIz. 2 of 2